BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

## "Schedule B"

**Name of Work :-** Providing and Installation poles and Lights to the GYM equipment area and play ground yard in Byatarayanapura constituency.

| Sl. No | Qty | Description Of Work | Unit | Quoted Rates | |
|---|---|---|---|---|---|
| | | | | In figures | In words |
| 1 | 16.00 | Fabricating, supplying and erection of ... ms long hot dip Galvanized Octagonal hot dip Pole with BSEN 10025 grade S 355 JO steel plate for shaft, IS 2062 for base plate with door opening arrangements,including suitable boards, Bakelite sheet and MCBs as per IS specifications suitable to withstand the wind speed of 47 m/s for .....m Pole in single section and single joint welded as per IS 9595/IS10178AWS having dimensions bottom ..... mm , top.... mm with 3 mm thick, suitable base plate and 4Nos of ..... long J bolts along with template and the Pole shall be hot dip galvanized in single dipping with not less than 65micron as per ASTM-A123 and 153 etc.,(excluding foundation) as per drawing appended 7 m - Top 70 mm and Bottom 130 mm dia | Each | 13500 | Thirteen Thousand Five Hundred Rupees |
| 2 | 86.00 | Supplying and fixing angle iron frame work fabricated out of M.S.angle iron.. and M.S. Flat.....with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint.50 x 50 x 6 mm | m | 395 | Three Hundred Ninety Five Rupees |
| 3 | 35.00 | Supply of LED floodlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate/clear glass material, delivering superior light output Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mauling with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100 V to 270V 50/60Hz application. Compliance to IS 10322/ IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with ..... W System Power consumption. LED Efficiency> 130lm/w, nominal CRI >75. Luminaire manufacturer should have in- house facility accredited by NABL / CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008. Housing with supplier word mark / name shall be Engraved / Embossing on the die cast housing / Body part Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer & Cree/Nichia/ Lumileds/Osram make LED Source. LED Floodlight 120W | Each | 10200 | Ten Thousand Two Hundred Rupees |
| 4 | 32.00 | Fixing halogen/metal halide /SVL/IL/LED floodlight fitting over existingpole /wall ceilingincluding clamps, bolts, nutsandwiring using suitable capacity wires. | Each | 162 | One Hundred Sixty Two Rupees |

For Sri Lakshmi Narasimha Electricals

Proprietor

Executive Engineer
Electrical Division
Yelahanka Zone BBMP
Byatarayanapura, Bangalore-92

| | | | | | |
|---|---|---|---|---|---|
| 5 | 16.00 | Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of Buildings & bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. Depth exceeding 1.5m, but not exceeding 3 m | $m^3$ | 259 | Two Hundred Fifty Nine Rupees |
| 6 | 299.00 | Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/ tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification.Buildings | Kgs | 89.45 | Eighty Nine Rupees and Forty Five Paise |
| 7 | 3.00 | Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates (15/ 2.1.3 Vol-1 KPWD SR 2023-24) | Cums | 5989 | Twelve Thousand Nine Hundred Eight One and Eight Piase |
| 8 | 13.50 | Providing and laying in position Cement Concrete for all Foundation works. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators, including all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all the other appurtenances required to complete the work as per technical specifications. M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (15/ 2.2.1 Vol-1 KPWD SR 2023-24) | Cums | 6287 | Seventy Eight Thousand Ninety Five Rupees |
| 9 | 0.20 | 1.1 kV, XLPE or Heat resistant PVC insulated, PVC exutruted Inner Seath Armoured LTUG Cable as per IS-1554 (Part 1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975. 25 Sqmm, 4 Core, (13 GI Strips - 4 x 0.8 mm) | KM | 179844 | Eighteen Thousand Two Hundred Fifty Rupees and Fifty three paise |
| 10 | 1.68 | 1.1 kV, XLPE or Heat resistant PVC insulated, PVC exutruted Inner Seath Armoured LTUG Cable as per IS-1554 (Part 1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975 16 Sqmm, 4 Core, (11 GI Strips - 4 x 0.8 mm) | KM | 141842 | Seventeen Thousand Nine Hundred Fifty Rupees and Five Paise |
| 11 | 3.00 | 1.1 kV Class HR (Heat Resistant) PVC Insulated & Sheathed Aluminium Single Core Lead wires as per IS-694: 2010 PVC Wire - 2.5 Sqmm Weight per 100 Mtr Coil: 1.8 Kg | Coil | 1484 | sixty One Thousand Six Hundred Seventy Eight Rupees |
| 12 | 9.00 | Rod type of earthing using 40 mm Dia, 3 Mtr long MS rod as ground rod, in earth pit of 300 mm width and 3300 mm depth and using 50x6 mm flat welded to ground rod as terminal & connected to equipment ground terminal using PVC Al wire as specified | No | 1950 | One Thousand Nine Hundred Fifty Rupees |
| 13 | 16.00 | Supply and Installation / Fixing / Provision of Outdoor type Thermoplastic Modular Panel enclosure with transparent Polycarbonate Lid, shock proof, IP65 (Weather Proof), rust proof, dust proof, water proof, corrosion proof having internally Embedded gasket on both lid and flap suitable to fix Single Phase / Three Phase Energy Meter in suitable base plate and having a provision for Fuse / MCB cut-out with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility.300 mm x 450 mm x 214 mm | Each | 5500 | Five Thousand Five Hundred Rupees |

For Sri Lakshmi Narasimha Electricals

Proprietor

Executive Engineer
Electrical Division
Yelahanka Zone BBMP
Byatarayanapura, Bangalore-9

| | | | | | |
|---|---|---|---|---|---|
| 14 | 16.00 | Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898 50-63 A DP | Each | 1000 | One Thousand Rupees |
| 15 | 10000.00 | Supplying and fixing hylum plastic sheet 3mm thick with necessary nitches for fixing switches, regulators etc., and fixing on existing wood or metal box using N. F. screws | cm2 | 0.35 | No Rupees and Thirty Five Paise |
| 16 | 1.88 | Laying of cable in Existing Trench/GI pipe/Stone Ware/RCC Hume pipe using Wooden/Aluminum Rollers as directed by the departmental staf2.5 to 25 Sqmm | KM | 20886 | Twenty Thousand Eight Hundred Eighty Six Rupees |
| 17 | 185 | Earth work excavation for pipeline trenches in all kinds of soils by mechanical means as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata.All kinds of soils. Depth upto 1.50 m | $m^3$ | 262 | Two Hundred Sixty Two Rupees |

I am prepared to take up the above work at rates quoted in the Schedule 'B'

For Sri Lakshmi Narasimha Electricals
Contractor

Proprietor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone